

## **Original Instruction Manual**

# SABRE-350 14" Bandsaw

Version 3.2
July 2017





# To register this product please visit **www.recordpower.info**

It is important to register your product as soon as possible in order to receive efficient after sales support and be entitled to the full **5 year guarantee**. Your statutory rights are not affected.

Please see back cover for contact details.







#### **Important**

For your safety read instructions carefully before assembling or using this product.

Save this manual for future reference.

### **Contents**

- 1 Explanation of Symbols
- 2 eneral ealth and Safety uidance
- 3 Additional ealth and Safety uidance for Bandsaws
- 4 Record Power uarantee
- **5** etting to now Your Bandsaw
- 6 Speci cations
- 7 Contents of the Package
- 8 Assembly
- 9 Operation and Bandsawing Practice
- **10** Maintenance
- 11 Dust Extraction
- **12** Troubleshooting
- **13** Electrical Connection and Wiring Diagram
- 14 Parts Diagrams and Lists
  - E" Declaration of Conformity

### 1. Explanation of Symbols

THE S MBOLS A D THEIR MEA I GS SHOW BELOW MA BE USED THROUGHOUT THIS MA UAL. PLEASE E SURE THAT OU TAKE THE APPROPRIATE ACTIO WHEREVER THE WAR I GS ARE USED.

#### Mandatory Instructions



Read and fully understand the instruction manual before attempting to use the machine.



Indicates an instruction that requires particular attention



Wear protective eyewear



"se respiratory protective equipment



" se hearing protection



" se suitable protective footwear



"se protective work gloves

#### Warning



Indicates a risk of severe personal injury or damage to the machine



Indicates a risk of severe personal injury from electrical shock



Risk of personal injury from lifting of heavy items



Indicates a risk of severe personal injury from airborne objects



Risk of re

### eneral ealth and Safety uidance

Ensure that you carefully read and fully understand the instructions in this manual before assembly, installation and use of this product. Keep these instructions in a safe place for future reference.

**WAR I G:** for your own safety, do not attempt to operate this machine until it is completely assembled and installed according to these instructions.

**WAR I G:** When using any machine, basic safety precautions should always be followed to reduce the risk of fire, electric shock and personal injury.

#### **Safe Operation**

#### 1. Use Personal Protective Equipment PPE

The operation of any machine can result in foreign objects being thrown into your eyes, which can result in severe eye damage. Protective eyewear or other suitable eye protection or face shield should be used at all times. Everyday spectacles only have impact resistant lenses. They are not protective eyewear and do not give additional lateral protection.

"se respiratory protective equipment dust mask etc. if the machining operation creates dust. Exposure to high levels of dust created by machining hardwoods, softwoods and man made composite boards can result in serious health problems. Some imported hardwoods give off highly irritating dust, which can cause a burning sensation. The use of respiratory protective equipment should not be seen as an alternative to controlling the risk of exposure at source by using adequate dust extraction equipment.

The use of ear plugs or ear defenders is recommended when the machine is in use, particularly if the noise level exceeds 85 dB.

Wear suitable protective gloves when handling cutting tools or blades. loves should OT be worn when using the machine as they can be caught in moving parts of the machine.

on-slip safety footwear is recommended when using the machine and handling large work pieces.

#### 2. Dress appropriately

Do not wear loose clothing, neckties or jewellery they can be caught in moving parts of the machine.

Roll up long sleeves above the elbow.

Wear protective hair covering to contain long hair.

#### 3. Safety warnings

Find and read any warning labels on the machine

It is important that any labels bearing health and safety warnings are not removed, defaced or covered. Replacement labels can be obtained by contacting our Customer Service Department.

#### 4. Familiarise yourself with the machine

If you are not thoroughly familiar with the operation of this machine, obtain advice from your supervisor, instructor, or other qualified person or contact your retailer for information on training courses. Do not use this machine until adequate training has been undertaken.

#### 5. Take care when moving or positioning the machine

Some machines can be very heavy. Ensure the floor of the area in which the machine is to be used is capable of supporting the machine.

The machine and its various components can be heavy. Always adopt a safe lifting technique and seek assistance when lifting heavy components. In some cases it may be necessary to use mechanical handling equipment to position the machine within the work area.

Some machines have optional wheel kits available to allow them to be manoeuvred around the workshop as required. Care should be taken to install these according to the instructions provided.

Due to the nature of the design of some machines the centre of gravity will be high making them unstable when moved. Extreme care should be taken when moving any machine.

If transportation of the machine is required then all precautions relating to the installation and handling of the machine apply. In addition, ensure that any vehicles or manual handling equipment used for transportation are of adequate specification.

#### 6. The machine should be level and stable at all times

When using a leg stand or cabinet base that is designed to be fitted to the machine, always ensure that it is securely fastened to the machine using the fixings provided.

If the machine is suitable to be used on a workbench, ensure that the workbench is well constructed and capable of withstanding the weight of the machine. The machine should always be securely fastened to the workbench with appropriate fixings.

Where possible, floor standing machines should always be secured to the floor with fixings appropriate to the structure of the floor.

The floor surface should be sound and level. All of the feet of the machine should make contact with the floor surface. If they do not, either re-locate the machine to a more suitable position or use packing shims between the feet and the floor surface to ensure the machine is stable.

#### 7. Remove adjusting keys and wrenches

Ensure that all adjusting wrenches and keys are removed before switching the machine O . There is a risk of severe personal injury or damage to the machine from airborne objects.

#### 8. Before switching the machine O

Clear the machine table of all objects tools, scrap pieces etc.

Make sure there is no debris between the work piece and the table / work support.

Ensure that the work piece is not pressed against, or touching the saw blade or cutting tool.

Check all clamps, work holding devices and fences to ensure that they are secure and cannot move during machining operations.

Plan the way that you will hold and feed the work piece for the entire machining operation.

#### 9. Whilst machining

Before starting work, watch the machine while it runs. If it makes an unfamiliar noise or vibrates excessively, switch the machine OFF immediately and disconnect it from the power supply. Do not restart until finding and correcting the source of the problem.

#### 10. Keep the work area clear

Working clearances can be thought of as the distances between machines and obstacles that allow safe operation of every machine without limitation. Consider existing and anticipated machine needs, size of material to be processed through each machine and space for auxiliary stands and/or work tables. Also consider the relative position of each machine to one another for efficient material handling. Be sure to allow yourself sufficient room to safely operate your machines in any foreseeable operation.

Cluttered work areas and benches create the risk of accidents. eep benches clear and tidy away tools that are not in use.

Ensure that the floor area is kept clean and clear of any dust and debris that may create trip or slip hazards.

#### 11. Consider the work area environment

Do not expose the machine to rain or damp conditions.

eep the work area well lit and ensure that there is artificial lighting available when there is insufficient natural light to effectively light the work area. Lighting should be bright enough to eliminate shadow and prevent eye strain.

Do not use the machine in explosive environments eg. in the presence of flammable liquids, gases or dust.

The presence of high levels of dust created by machining wood can present a risk of fire or explosion. Always use dust extraction equipment to minimise the risk.

#### 12. Keep other persons away and pets

The machine is designed to be used by one person only.

Do not let persons, especially children, touch the machine or extension cable if used and keep visitors away from the work area.

ever leave the machine running unattended. Turn the power supply off and do not leave the machine unattended until it comes to a

### 2. eneral ealth and Safety uidance

complete stop.

If the work area is to be left unattended, all machinery should be switched OFF and isolated from the mains power supply.

#### 13. Store machines safely when not in use

When not in use, machines should be stored in a dry place, out of reach of children. Do not allow persons unfamiliar with these instructions or with the machine to operate it.

#### 14. Do not overreach

Choose a working position that allows your body to remain balanced and feed the work piece in to the machine without overreaching.

eep proper footing and balance at all times.

#### 15. Electrical supply

Electrical circuits should be dedicated to each machine or large enough to handle combined motor amp loads. Power outlets should be located near each machine so that power or extension cables are not obstructing high-traffic areas. Observe local electrical guidelines for proper installation of new lighting, power outlets, or circuits.

The machine must be connected to an earthed power supply.

The power supply must be equipped with a circuit breaker that provides short circuit, overload and earth leakage protection.

The voltage of the machine must correspond to the voltage of the mains power supply.

The mains plug fitted to the machine should always match the power outlet. Do not modify the plug in any way. If a replacement plug is required it should be fitted by a competent person and of the correct type and rating for the machine.

If you are unsure about any electrical connections always consult a qualified electrician.

#### 16. Avoid unintentional starting of the machine

Most machines are fitted with a no-volt release VR switch to prevent unintentional starting. If in doubt always ensure the machine switch is in the OFF position before connecting it to the power supply. This means the machine will not automatically start up after a power cut or switching on of the power supply, unless you first reset the start switch.

#### 17. Outdoor use

Your machine should not be used outdoors.

#### 18. Extension cables

Whenever possible, the use of extension cables is not recommended. If the use of an extension cable is unavoidable, then it should have a minimum core cross section of 2.5 mm and limited to a maximum length of 3 metres.

Extension cables should be routed away from the direct working area to prevent a trip hazard.

#### 19. Guard against electric shock

Avoid body contact with earthed or grounded surfaces such as pipes and radiators. There is an increased risk of electric shock if your body is earthed or grounded.

#### 20. Always work within the machine s intended capacities

Operator safety and machine performance are seriously adversely affected if attempts to make the machine perform beyond its limits are made.

#### 21. Do not abuse the power cable

ever pull the power cable to disconnect it from the power socket. Always use the plug.

eep the power cable away from heat, oil and sharp edges.

Do not use the power cable for carrying or moving the machine.

#### 22. Secure the work piece

damaged, replace it immediately.

Ensure that the work piece is securely held before starting to machine it. When working within 300 mm of the machining area, always use a push stick to feed the work piece in to the blade or cutting tool. The push stick should have a minimum length of 400 mm. If the push stick becomes

"se extra supports roller support stands etc. for any work pieces large enough to tip when not held down to the table top.

Do not use another person as a substitute for a table extension, or as additional support for a work piece that is longer or wider than the basic table, or to help feed, support, or pull the work piece.

Do not attempt to machine more than one work piece at a time.

When feeding the work piece towards the blade or cutting tool never position your hands in direct line of the cutting path. Avoid awkward operations and hand positions where a sudden slip could cause your hand or fingers to move into the machining area.

#### 23. Stay alert

Safety is a combination of operator common sense and alertness at all times when the machine is being used.

" se all machines with extreme care and do not use the machine when you are tired or under the influence of drugs, alcohol or medication.

#### 24. Use the correct tool for the job

Do not use the machine for any purpose other than which it was designed.

When selecting replacement cutting tools and blades, always ensure that they are designed to cut the material that you intend to use them for. If in any doubt seek further advice from the manufacturer.

#### 25. Connect dust extraction equipment

Always use dust extraction equipment. The dust extractor should be of suitable size and capacity for the machine that it is connected to and have a filtration level appropriate to the type of waste being collected. Refer to the relevant section of the manual for details of the specific dust extraction requirements for this machine.

The dust extractor should be switched O before starting the machine that it is connected to. The dust extractor should be left running for 30 seconds after the last machining operation is complete in order to clear any residual waste from the machine.

#### 26. Ensure that the machine is correctly guarded

ever use the machine if any of the standard safety guards and equipment are removed or damaged.

Some machines incorporate safety interlocks to prevent the machine from being used without the guards in place. ever attempt to bypass or modify the interlocks to allow the machine to be used without the guards in place.

#### 27. Maintain your machine with care

This manual gives clear instructions on installation, set up and operation of the machine and also details any routine and preventative maintenance that should be performed periodically by the user.

Remember always to switch off and unplug the machine from the power supply before carrying out any setting up or maintenance operations.

Follow any instructions for the maintenance of accessories and consumables.

Do not use compressed air to clean the machine. Always use a brush to dislodge dust in places that are awkward to reach and a dust extractor to collect the waste.

Inspect electric cables periodically and, if damaged, have them replaced by an authorised service facility or qualified electrician.

Inspect extension cables if used periodically and replace if damaged.

#### 28. Keep cutting tools sharp and clean

Correctly maintained cutting tools are easier to control and less likely to hind

Cutting tools and blades can become hot during use. Take extreme care when handling them and always allow them to cool before changing, adjusting or sharpening them.

#### 29. Disconnect the machine from the power supply

When not in use, before servicing, changing blades etc. always disconnect the machine from the power supply.

#### 30. Check for damaged parts

Before each use of the machine, it should be carefully checked to determine that it will operate properly and perform its intended function.

### 2. eneral ealth and Safety uidance

Check for alignment of moving parts, binding of moving parts, breakage of parts and any other conditions that may affect the operation of the machine.

A guard or other part that is damaged should be properly repaired or replaced by a qualified person unless otherwise indicated in this instruction manual.

Do not use the machine if the switch does not turn the machine  $\, O \,$  and  $\, OFF \,$ .

ave defective switches replaced by a qualified person.

#### 31. Warning

The use of any accessory or attachment, other than those recommended in this instruction manual, or recommended by our Company may present a risk of personal injury or damage to the machine and invalidation of the warranty.

#### 32. Have your machine repaired by a qualified person

This machine complies with the relevant safety rules and standards appropriate to its type when used in accordance with these instructions and with all of the standard safety guards and equipment in place. Only qualified persons using original spare parts should carry out repairs. Failure to do this may result in considerable danger to the user and invalidation of warranty.

#### 33. Caution Motor may become hot during use

It is normal for motors on some machines to become hot to the touch during use. Avoid touching the motor directly when in use.

### 3. Additional ealth and Safety uidance for Bandsaws

#### **Safe Operation**

#### 1. Familiarise yourself with the machine

Machining operations using bandsaws have a history of serious accidents. Most result from contact with the moving blade while presenting material to the blade or moving it from the table. Other minor accidents can occur whilst setting, cleaning, adjusting or maintaining the machine.

The machine is designed for cutting wood and composite board plywood, MDF etc. . Certain plastics can also be cut using a suitable blade.

#### 2. Before switching the machine O

Ensure that the blade is correctly tensioned and aligned on the bandwheels and the blade guides are correctly adjusted.

Ensure that the teeth of the blade are pointing downwards.

Check the condition of the blade to ensure that no teeth are missing, damaged or deformed and the blade is not cracked or split. If any of these conditions apply, replace the blade immediately.

Ensure that the saw blade type and width are suitable for the material to be cut.

Check that the blade width is within the minimum and maximum permitted on the machine and that the thickness of the blade is suitable for the diameter of the wheel.

Some machines have more than one cutting speed. For most wood cutting applications the faster of the speeds should be used.

Check the condition of the table insert. Replace it immediately if it is damaged or showing signs of wear.

Adjust the guard as close as possible to the work piece being cut.

Check that access doors are fully closed and that the latches are secure.

#### 3. Whilst machining

ever apply sideways pressure to the blade as this may cause the blade to break.

Care must be taken when cutting wood with knots, nails or cracks in it and / or dirt on it, as these can cause the blade to get stuck. If this happens, switch the machine OFF immediately and follow the procedure detailed in the manual to remove the blade from the work piece.

If cutting cylindrical timber use a suitable jig to prevent twisting of the work piece.

**4.** This machine falls under the scope of the ealth and Safety at Work etc. Act 1974, and the Provision "se of Work Equipment Regulations 1998. In addition the elimination or control of risks from wood dust is included in the above regulations and the Control of Substances azardous to ealth COS Regulations 2002. We recommend that you study and follow these regulations.

Further guidance can be found in the Safety in the use of narrow bandsaws Woodworking sheet o.31 and the Safe use of woodworking machinery code of practice booklet L114 published by ealth and Safety Executive and available from their website www.hse.gov.uk.

### 4. Record Power uarantee

**Products** means the Products sold by Record Power subject to these terms and conditions

**Record Power** is Record Power Limited, whose company registration number is 4804158 and registered office address is Centenary ouse, 11 Midland Way, Barlborough Links, Chesterfield, Derbyshire, S43 4 A and sells through a network of Authorised Dealers

**Authorised Distributor** is the nominated importer for your region who will generally sell through a network of Authorised Dealers. Details of Authorised Distributors for specific countries can be found in the Product manual or at www.recordpower.info

**Authorised Dealer** is a retailer or business authorised to sell Record Power Products to end users.

#### 1 Guarantee

- 1.1 Record Power guarantees that for a period of 5 years from the date of purchase the components of qualifying Products see clauses 1.2.1 to 1.2.9 will be free from defects caused by faulty construction or manufacture
- 1.2 During this period Record Power, its Authorised Distributor or Authorised Dealer will repair or replace free of charge any parts which are proved to be faulty in accordance with paragraphs 1.1 above provided that
- **1.2.1** you follow the claims procedure set out in clause 2 below
- 1.2.2 Record Power, our Authorised Distributor or Authorised Dealer are given a reasonable opportunity after receiving notice of the claim to examine the Product
- 1.2.3 if asked to do so by Record Power, its Authorised Distributor or Authorised Dealer, you return the Product, at your own cost, to Record Power's premises or other approved premises such as those of the Authorised Distributor or supplying Authorised Dealer, for the examination to take place
- **1.2.4** the fault in question is not caused by industrial use, accidental damage, fair wear and tear, wilful damage, neglect, incorrect electrical connection, abnormal working conditions, failure to follow our instructions, misuse, or alteration or repair of the Product without our approval
- 1.2.5 the Product has been used in a domestic environment only
- 1.2.6 the fault does not relate to consumable Products such as blades, bearings, drive belts or other wearing parts which can reasonably be expected to wear at different rates depending on usage for full details contact Record Power or your local Authorised Distributor
- **1.2.7** the Product has not been used for hire purposes, by you or by a previous owner
- **1.2.8** the Product has been purchased by you as the guarantee is not transferable from a private sale.
- **1.2.9** where the Product has been purchased from a retailer, the 5 year guarantee is transferable and begins on the date of the first purchase of the Product and in the event of a claim under this guarantee proof of the original purchase date will be required to validate the warranty period.

#### 2 Claims Procedure

- 2.1 In the first instance please contact the Authorised Dealer who supplied the Product to you. In our experience many initial problems with machines that are thought to be due to faulty parts are actually solved by correct setting up or adjustment of the machines. A good Authorised Dealer should be able to resolve the majority of these issues much more quickly than processing a claim under the quarantee.
- **2.2** Any damage to the Product resulting in a potential claim under the guarantee must be reported to the Authorised Dealer from which it was purchased within 48 hours of receipt.
- 2.3 If the Authorised Dealer who supplied the Product to you has been unable to satisfy your query, any claim made under this uarantee should be made directly to Record Power or its Authorised Distributor for details of the Authorised Distributor in your country please see your Product manual or check www.recordpower.info for details . The claim itself should be made in a letter setting out the date and place of purchase, and giving a brief explanation of the problem which has led to the claim. This letter should then be sent with proof of the purchase date preferably a receipt to Record Power or its Authorised Distributor. If you include a phone number or email address this will help to speed up your claim.
- Please note that it is essential that the letter of claim reaches Record Power or its Authorised Distributor on the last day of this uarantee at the latest. Late claims will not be considered.


#### 3 Limitation of Liability


- **3.1** We only supply Products for domestic and private use. You agree not to use the Product for any commercial, business or re-sale purposes and we have no liability to you for any loss of profit, loss of business, business interruption or loss of business opportunity.
- **3.2** This uarantee does not confer any rights other than those expressly set out above and does not cover any claims for consequential loss or damage. This uarantee is offered as an extra benefit and does not affect your statutory rights as a consumer.

#### 4 otice

This uarantee applies to all Products purchased from an Authorised Dealer of Record Power within the "nited ingdom of reat Britain and orthern Ireland. Terms of uarantee may vary in other countries please check with the Authorised Distributor in your country details of the Authorised Distributor for your country can be found in the manual or at www.recordpower.info .

### 5. etting to now Your Bandsaw





- 1 On / off switch
- **2** Rip fence assembly
- 3 Blade tensioning knob
- 4 uide post cap
- **5** "pper door knob
- 6 "pper blade guides
- **7** Blade
- 8 Table
- 9 Lower door knob
- 10 Dust extraction port

- 11 Table locking lever
- 12 Trunnion
- 13 Blade guide position hand wheel
- **14** Blade guide lock
- **15** Blade tracking knob lock
- **16** Blade tracking knob
- 17 Cam tension lever
- **18** Table tilt box wrench
- 19 Motor

### 6. Specifications

Maximum depth of cut: 285 mm Throat depth: 345 mm Table si e: 546 x 400 mm Table height from oor: 1029 mm Motor input P1: 1.5 kW

Motor output P2: 1.1 kW

Sound power level: 2 100 dBA Sound pressure level: 2 90 dBA Main document number: RC1401 Voltage: 230 V Frequency: 50 z Full load current: 6.2 A Short circuit raiting: 1 kA Motor speed: 1400 rpm Blade length: 111 2820 mm

Associated uncertanty 4 dB measurement made in accordance with E ISO 3746 2010

Blade width capacity: 1/4 6.35 mm - 3/4 19 mm Blade speed: 440 m / minute and 1000 m / minute Extraction port internal diameter: 93 mm Extraction port external diameter: 99 mm

Weight: 116 kg

Si e: 1892 x W870 x D656 mm

The gures quoted are emission levels and are not necessarily safe working levels. Whilst there is a correlation between the emission and exposure levels, this cannot be used reliably to determine whether or not further precautions are required. Factors that in uence the actual level of exposure of the workforce include the characteristics of the work room and the other sources of noise, etc., i.e. the number of machines and other adjacent processes.


Also the permissible exposure level can vary from country to country. This information, however, will enable the user of the machine to make a better evaluation of the hazard and risk.

# 7. Contents of the Package



1	Sabre-350 Bandsaw	1	11	Push stick	1	21	M8 nut	1
2	Table with levelling pin attached	1	12	and wheels	2	22	M6 x 30 hex socket head screw	1
3	ex head socket screws	4	13	Rip fence	1	23	M6 nut	1
4	Washers	4	14	uide post cap	1	24	Power cord "plug shown	1
5	Spring washers	4	15	Blade tensioning knob	1	25	3 mm hex wrench	1
6	Rip fence rail and fixings	1	16	Tool holder	1	26	4 mm hex wrench	1
7	Rip fence mount	1	17	M5 x 10 mounting screws	2	27	5 mm hex wrench	1
8	17/19 mm wrench	1	18	Re-saw bar assembly	1	28	6 mm hex wrench	1
9	13 mm wrench	1	19	Box wrench	1			
10	10 mm wrench	1	20	M8 x 50 hex head bolt	1			

# 7. Contents of the Package



1	Cabinet base panel	1
2	Cabinet right hand side panel	1
3	Cabinet shelf	1
4	Cabinet door	1
5	Cabinet cross beam	2
6	Cabinet back panel	1
7	Cabinet left hand side panel	1
8	ex head countersunk socket screws	4
9	M6 nylon locking nut	2
10	Bushing	1
11	M6 x 16 hex head socket screw	1
12	M6 x 20 hex head socket screw	1
13	M8 x 20 flanged hex head bolt	16
14	Washer	2
15	Cabinet door handle	1



Important: Do not fully tighten the fixings until the cabinet is fully assembled.

#### **Assembling the Cabinet Base**


The cabinet base features a set of 3 holes in each corner as shown in **Fig 8.1**. The side of the cabinet which has the innermost holes located 75 mm from the edge of the base as shown must be used as the front of the cabinet.


Attach the door handle to the right-hand side panel with the M6 x 20 hex head socket screw and an M6 nylon locking nut as shown in **Fig 8.2**, using the 10 mm wrench and 5 mm hex wrench. Do not fully tighten as rotation of the handle is necessary to hold the door closed once fully assembled.


Attach the left-hand side panel to the base as shown in **Fig 8.3**, using 2 M8 x 20 flanged hex head bolts.

Attach the right-hand side panel to the base as shown in **Fig 8.4**, using 2 M8  $\times$  20 flanged hex head bolts.


Attach an M8 x 20 flanged hex head bolt to the front bottom and top of both side panels as shown in **Fig 8.5**. Leave a gap of approximately 3 mm between the flanges and the panel as shown.











Fit the cabinet cross beams to the top and bottom of the front of the side panels as shown in **Fig 8.6** and ensure the notches are positioned horizontally as shown and tighten the bolts enough to keep the cross beams in place.


Attach 3 M8  $\times$  20 flanged hex head bolts to the back of each side panel as shown in **Fig 8.7**. Leave a gap of approximately 3 mm between the flanges and the panels as shown.


Fit the back panel to the cabinet as shown in **Fig 8.8** and tighten the upper and lower bolts enough to keep the panel in place. Leave the centre bolts loose until the shelf has been fitted.

Attach an M8 x 20 flanged hex head bolt and washer to the front centre of each side panel as shown in **Fig 8.9**. Leave a gap of approximately 3 mm between the flanges and the washers as shown.


Install the shelf as shown in **Fig 8.10** by placing it over the central bolts in the side panels. The washers act as spacers to ensure correct alignment of the cabinet components.

Fully tighten all fixings with the 13 mm wrench to secure the structure of the cabinet base.











Place the door onto the left-hand side panel as shown in Fig 8.11.

Attach the M6 x 16 hex head socket screw, bushing and nylon locking nut to the door as shown in **Fig 8.12** using the 10 mm wrench and 5 mm hex wrench.

Close the cabinet door ensuring the handle locates around the screw on the door to keep it closed. The cabinet base is now fully assembled as shown in **Fig 8.13**.

#### **Attaching the Bandsaw to the Cabinet Base**






Warning: The bandsaw is very heavy and should be assembled by two people.


It is recommended to carefully lay the bandsaw on its back as shown in **Fig 8.14** onto blocks of wood to protect it from damage. Ensure the edge of the bandsaw base is aligned with the edge of the block of wood as shown in **Fig 8.15**.











Secure the base to the bandsaw using the 4 hex head countersunk socket screws as shown in **Fig 8.16**.

Carefully raise the bandsaw to the upright position and remove the blocks of wood

The table trunnion has 4 holes as shown in **Fig 8.17** and the underside of the table has 4 corresponding threaded holes as shown in **Fig 8.18**. Place the table onto the trunnion as shown in **Fig 8.19**, taking care to pass the blade through the table slot without damaging it.




### Ensure the blade slot in the table is aligned centrally with the blade.


Secure the table in place using 4 hex head socket screws, washers and spring washers as shown in **Fig 8.19**. Do not fully tighten until the table is aligned with the blade.


#### Aligning the Table to the Blade

For accurate cutting the table must be parallel to the bandsaw blade. Place a straight edge along the blade as shown in **Fig 8.20** then measure the distance between the straight edge and the mitre fence slot in the table as shown. When the distance are equal at the front and back of the mitre slot the screws can be tightened fully.


Once tightened, check the alignment and re-adjust if necessary.











#### Positioning the Table at 90 to the Blade

Loosen the table lock lever as shown in **Fig 8.21** and use the box wrench to tilt the table to gain access to the underside.

Place the M8 nut onto the M8 x 50 hex head bolt and attach to the underside of the table as shown in **Fig 8.22**. This bolt acts as a table stop to ensure the table returns to the correct position when it is required to be at 90 to the blade.


Set the stop bolt so that the table is 90 when in contact with the swivelling heel block. This is rotated out of the way of the stop bolt when you require the table to be set beyond 0 on the angle scale of the trunnion.


Set the table at 90 to the blade using a square as shown in **Fig 8.23**. Secure it in place then adjust the screw so that it touches the top of the lower band wheel box. Secure the screw in place by tightening the nut against the table surface.


If necessary the angle scale pointer can now be adjusted to point to 0 as shown in **Fig 8.24** using a Phillips screwdriver.


#### **Installing the Rip Fence**


Fit the rip fence rail to the table as shown in **Fig 8.25** using the nuts and washers supplied with the rail in the order shown in **Fig 8.26**.












Ensure the rip fence rail is parallel to the table by measuring the distance between them at one end as shown in **Fig 8.27** and ensure the measurement is the same at the opposite end as shown in **Fig 8.28**.



Important: Ensure at this stage the table levelling pin is installed as shown in Fig 8.29.


To ensure the **height of the rail is parallel** to the table lay a steel rule on the table surface as shown in **Fig 8.30** and measure the distance between the rule and the rail.












Repeat this process at the opposite end of the table as shown in **Fig 8.31**, ensuring both measurements are equal.

#### **Fitting the Fence**


Place the rip fence mount onto the rail as shown in Fig 8.32.


Slide the rip fence onto the mount as shown in **Fig 8.33**. Ensure the rip fence is placed fully onto the mount and locates over the protrusion as shown in **Fig 8.34**.


Secure the rip fence in place using the fence lock knob as shown in **Fig 8.35**. The fence and mount assembly is secured in place on the rail using the position lock knob as shown in **Fig 8.35**.












The fence can also be fitted as shown in **Fig 8.36**. This position allows the guides to move much further down to support the blade when cutting thinner materials.


The fence features a pad at each end as shown in **Fig 8.37**. This raises the fence from the table to minimise contact and improve travel of the fence across the table and mitre slot.


**The height of the fence should be parallel** with the table as shown in **Fig 8.38**. If adjustment is required, change the height of the rip fence rail as previously described until the fence is positioned as shown.


**Mounting the Rip Fence to the Right Hand Side of the Blade**To support work when cutting with the table tilted, the rip fence can be placed to the right hand side of the blade.

Remove the rip fence from the mount. Fully unscrew the fence lock knob and remove the knob assembly and T bar as shown in **Fig 8.39**. Re-fit to the opposite side of the fence mount as shown in **Fig 8.40**.











Re-fit the rip fence to the mount as previously described and shown in **Fig** 8.41

#### Aligning the Fence with the Blade


For accurate cutting the rip fence must be parallel to the blade as shown in **Fig 8.42**. The fence mount features a cam-mechanism adjustment for quick and easy alignment.


Loosen the lock knob as shown in **Fig 8.35** and use the adjustment knob to move the fence. The fence can be moved anti-clockwise as shown in **Fig 8.43** or clockwise as shown in **Fig 8.44**. When the fence is in the desired position re-tighten the lock knob.


#### **Fitting the Blade Tensioning Knob**


Place the tension knob onto the tensioning shaft as shown in Fig 8.45.











#### **Fitting the Guide Post Cap**


The guide post cap must be installed before use of the bandsaw. Its purpose is to keep the guide post covered when the guides are in the highest positions as the post will protrude from the upper band wheel box. Place the cap over the hole in the upper band wheel box as shown in **Fig 8.46** and press down until it clicks into place.


#### **Fitting the Hand Wheels**

The 2 hand wheels supplied must be fitted as shown in **Fig 8.47**. The hand wheel which fits to the upper band wheel box operates the guide post and the one fitted to the lower band wheel box controls the drive belt tension.

Both hand wheel shafts feature a flattened area as shown in **Fig 8.48**. Place the upper hand wheel onto the shaft as shown in **Fig 8.49**, ensuring the blind set screw is positioned over the flattened area. Tighten the blind set screw to secure the hand wheel in place using a 3 mm hex wrench.


Fit the remaining hand wheel to the lower band wheel box as shown in **Fig 8.50**.











#### **Fitting the Push Stick Holder**

Screw the M6 x 30 hex socket head screw to the bandsaw frame as shown in **Fig 8.51** and secure in place with the M6 nut. Place the push stick holder onto the screw as shown in **Fig 8.52**.

#### **Fitting the Tool Holder**

Secure the tool holder to the rear of the bandsaw spine as shown in **Fig 8.53** using the 2 M5 x 10 mounting screws supplied. The tool holder is used for storing the hex wrenches supplied with the machine as shown in **Fig 8.54**.

#### **Fitting the Re-Saw Bar**

The re-saw bar can be used when cutting timber which is prone to variations in density and grain direction, particularly larger pieces. The bar is used to pivot the timber against so the feed direction can be adjusted by the operator to ensure the straightest possible cut.

Disassemble the re-saw bar assembly and place the bar through the slots in the fence as shown in **Fig 8.55**. Re-fit the fixings as shown and secure the bar in place.

















Caution: Before carrying out any adjustments or maintenance ensure that the machine is isolated and disconnected from the electricity supply.

#### **Changing the Bandsaw Blade**

Open the upper and lower band wheel box doors.

Remove the securing table levelling pin as shown in **Fig 9.1** to allow the blade to be passed through the front of the table as it is removed.


Move the cam tension lever to the left as shown in Fig 9.2.


Wearing protective gloves, carefully remove the blade by pulling it forwards and out from the table slot as shown in **Fig 9.3**. Ensure the left hand side of the blade is brought through the gap in the spine blade cover as shown in **Fig 9.4**.

Fit the new blade to the bandsaw, ensuring the teeth of the blade point downwards and towards the front of the machine as shown in **Fig 9.5**.

ote: If the new blade is the same si e and type as the old blade, the blade tension and guide positions may not necessarily need adjusting.











#### **Tensioning the Bandsaw Blade**

Re-engage the cam tension lever and if necessary adjust the tension knob to apply the correct tension to the blade.

To check the tension of the blade, set the blade guides to their highest position and apply a reasonable amount of pressure using a push stick. A correctly tensioned blade will move approximately 4 mm as shown in **Fig 9.6**. Do not overtighten the blade as shown in **Fig 9.6** as this could damage it.

The machine features a blade tension indicator as shown in **Fig 9.7**. This gives an approximate guide to the tension required for a variety of blade sizes.

Bandsaw blade tension can be subject to personal preferences and opinions vary on the best ways to measure the tension and of what the correct tension should be. If the blade is cutting accurately then this is the best indication that the tension and overall machine setup is correct. If adjusting the blade tension does not correct a poorly performing blade, this could indicate that the blade needs replacing.


If the machine is not in use for long periods, slacken the tension to avoid placing unnecessary pressure on the blade and the bandsaw itself.


#### **Tracking the Bandsaw Blade**


A correctly tracked blade will sit centrally on the band wheels as shown in **Fiq 9.8**.


To adjust the tracking, loosen the tracking lock knob and adjust the tracking knob as shown in **Fig 9.9**. Turn the knob clockwise to move the blade towards the back of the band wheel and anti-clockwise to move it towards the front. Rotate the bandwheels by hand to move the blade into position. Once the tracking is set correctly re-tighten the tracking lock knob.

To aid tracking there is an inspection window on the side of the upper band wheel box as shown in **Fig 9.10** which allows the blade position to be seen.











#### **Setting the Blade Guides**

Once the blade is installed, tensioned and tracked the guides must be set correctly around it.

There are 2 sets of guides on the bandsaw, one above the table and one below. Both sets comprise a pair of guides on either side of the blade and a rear guide. All guides are spring-loaded for easy adjustment.

The side guides should be positioned so they are just behind the blade gullet. This will ensure the teeth do not catch on the guides during operation. See **Fig 9.11**.

In addition, the side guides should also be positioned as close to the blade as possible but without touching the blade. The guides should not be touching the blade when the machine is running and not under load as constant contact will reduce the life span of the blade, See **Fig 9.12**.

The rear guide must also be placed as close as possible to the blade but not be touching it, see **Fig 9.13**.





Important: When positioning the side guides behind the blade gullet take into account the possible backwards movement of the blade during cutting to ensure that the side guides do not protrude past the gullet.


#### **Adjusting the Upper Blade Guides**


To move the side guides to the correct position behind the blade gullet, loosen the guide assembly lock shown in **Fig 9.14** and move the whole guide assembly until the guides are positioned correctly then re-tighten the quide assembly lock.


The side guides must now be positioned as close to either side of the blade as possible. Loosen the side guide locks shown in **Fig 9.14**, position the guides correctly my moving the guide shafts then re-tighten the locks as shown in **Fig 9.15**.











The rear guide must now be set in the correct position. Loosen the rear guide lock shown in **Fig 9.14** and position the guide by moving the guide shaft as shown in **Fig 9.16**.

#### **Adjusting the Lower Blade Guides**

The lower guides are set in the same way as the upper guides. The guide assembly differs to the upper assembly as there is a ratchet handle that must be loosened to allow movement of the guide assembly, see **Fig 9.17**.


#### **Setting the Height of the Upper Blade Guides**


The upper guide assembly should be set as low as possible for the cut being made to give maximum support to the blade and aid in accurate cutting.


To move the guide assembly, loosen the blade guide lock as shown in **Fig 9.18** and use the blade guide position hand wheel to raise or lower the assembly to the required height. Re-tighten the blade guide lock to ensure the guide assembly remains in place.


The blade guard features a scale as shown in **Fig 9.19**. This indicates the height of the bottom of the blade guides from the table to aid positioning.


The assembly must allow the workpiece to pass beneath it as shown in Fig 9.20.











#### Turning the Bandsaw On and Off

The bandsaw is fitted with a no-volt release switch which ensures it will not unintentionally re-start after a power failure, **Fig 9.21**.

To turn the machine on press the blue button marked On .

To turn the machine off press the red button marked Off .




#### **Changing the Speed of the Bandsaw**


The SABRE-350 can run at either 440.5 m / min or 899.2 m / min. The higher speed is suitable for cutting wood and the lower speed is suitable for cutting non-ferrous metals. To change speed open the lower band wheel box door as shown in **Fig 9.22** and loosen the drive belt tension by turning the belt tension hand wheel clockwise as shown.


To set the machine at the lower speed, position the drive belt on the lower band wheel pulley and motor shaft pulley as shown in **Fig 9.23**.

To set the machine at the higher speed, position the drive belt on the lower band wheel pulley and motor shaft pulley as shown in **Fig 9.24**.

When changing the position of the drive belt ensure that it is also placed over the tension pulley as shown in **Fig 9.22**.







#### **Basic Bandsawing Principles**

The blade cuts on a continuous down stroke.

Slowly feed the workpiece towards the blade, using only light pressure whilst letting the blade do the cutting. Always use a push stick and take care.

Firmly hold the workpiece and feed it towards the blade slowly, using the push stick and keeping your hands well away from the blade.

For best results the blade must be sharp. Damaged or worn blades should always be replaced.

Select the correct blade for the job, depending on the thickness of the wood and the cut to be made see blade selection .

For straight cutting use the rip fence supplied.

When cutting shapes, follow the design marked out by pushing and turning the workpiece evenly. Do not attempt to turn the workpiece without pushing it, as this may cause the workpiece to get stuck, or the blade to bend.



**CAUTIO** Particular care should be taken towards the end of the cut as there will be a sudden decrease in resistance and care must be taken to stop hands from being thrown towards the blade. Always use a push stick.

Always ensure that your machine is properly maintained and clean. Before commencing work on an important project, it is advisable to familiarise yourself with the operation of the equipment by practising on low value or scrap materials.



**WAR I G** In circumstances such as cutting deep or wet timber, the work piece may close up behind the blade causing it to stall. In the event that the blade stalls whilst cutting, ease the work piece backwards slightly, to release feed pressure from the blade. Allow the blade to reach full speed before continuing to feed the work piece in to the blade. If the blade fails to move when feed pressure is released, immediately switch off the machine and disconnect the power supply before attempting to free the blade from the work piece.



**WAR I G** If any component of the machine fails whilst in use or if the blade should break whilst the machine is running, immediately switch off the machine and disconnect from the power supply. Remove the faulty component and replace only with genuine Record Power replacement parts. Any electrical components should only be replaced by a suitably quali ed person. To replace a broken blade, please refer to the section of this manual entitled Band saw Blade Set "p . Always remember to fully release the blade tension mechanism before attempting to t a new blade. If you are in any doubt about using the machine following a failure or if you need to order replacement spare parts or blades, please contact customer services in your country.

#### Restarting

#### In the Event of a Blockage or if the Machine Stalls

If the bandsaw stalls due to the blade becoming trapped in the work piece, switch it off immediately by pressing the stop button and wait for the machine to come to a complete stop before proceeding further. If the blade is trapped within the work piece, it may be necessary to prize the work piece apart slightly using a suitable lever or wooden wedge in order to free the blade. If it is not possible to free the blade using this method, then it may be necessary to cut the blade using suitable side cutters or tin snips.

Replace the blade if necessary and ensure that it is correctly tracked and tensioned and that both doors of the bandsaw are fully closed and secured before attempting to re-start the machine.

To re-start the machine, press the green button marked I on the switch.

#### In the Event of a Power Failure

The bandsaw is fitted with a no volt release VR switch to protect the user against automatic starting of the machine when power is restored after a power failure.

In the event of a power failure, first locate and rectify the source of the failure. If the fault is within the power circuit of the workshop, there may be an underlying cause circuit overload etc. that should be investigated by a qualified electrician, before attempting to restore the power source. If a cutting operation was taking place when the power supply was interrupted, then it may be necessary to free the blade from the work piece before attempting to re-start the machine.

Once the power is restored, the machine can be re-started by pressing the green button marked I on the switch.

#### **Blade Selection TPI**

The selection of the best blade configuration see page 28 is necessary for optimum cutting performance.

Correct blade choice is primarily dependant on two factors material thickness and material type.

reater TPI should be selected as material thickness decreases.

owever, if the TPI is too great, the tooth loading will be insufficient to enable penetration and cutting. The teeth will also rapidly lose their sharpness.

For thicker material a lower TPI should be used otherwise the gullet will not be sufficient to clear the waste and the blade will stall or burn the wood.

In general a minimum of 3 teeth should be in contact with the wood at all times during cutting.

The accompanying blade selection chart see the table below gives guidance on the TPI that should give the best results when cutting a variety of material types and thickness. The table below provides recommendations on selecting the correct blade for a variety of commonly used materials. If in doubt about any aspects of blade selection contact Customer Services in your country.

The table provides a guide to selection only. Exact tooth configurations are not always available, nor are all blade configurations covered, but the principles remain the same.

For special applications, custom blades can be supplied please call Customer Services in your country and we can advise you accordingly on your specific needs.

Material	Material Thickness						
-	6 mm	6-12 mm	12-25 mm	25mm			
Perspex	16 TPI	14 TPI	-				
Chipboard	-	6 TPI	3-6 TPI	3-4 TPI			
Fibre board	16 TPI	14 TPI	-	-			
ardboard	10 TPI	-	-	-			
Plywood	10 TPI	8 TPI	6 TPI	3-4 TPI			
Strawboard	14 TPI	10 TPI	-	-			
Cork	14 TPI	6 TPI	3 TPI	3-4 TPI			
Leather	14 TPI	-	-	-			
Rubber	10 TPI	8 TPI	-	-			
Wood -log	-	-	-	3-4 TPI			
Wood -soft	6 TPI	3-6 TPI	3-4 TPI	3-4 TPI			
Wood -hard	6 TPI	3-6 TPI	3-4 TPI	3-4 TPI			
Wood -wet	-	-	-	3-4 TPI			

#### Blade Selection TPI - Cont.

aving selected an appropriate blade for the particular thickness and type of material to be sawn, it is essential that the saw blade is allowed to cut freely by not applying too much pressure.

The need for excessive pressure is likely to be a result of the incorrect blade selection or a worn blade and will result in inaccurate cutting and possibly blade breakage.


#### **Blade Selection Width**

When cutting shapes, the width of the blade limits the minimum radius that can be cut.

If the blade is too wide for the cutting radius the blade will twist and possibly jam or break.

The smaller the radius the narrower the blade has to be.

The diagram below provides guidance on the minimum radius to be cut with the most commonly used blade widths.



#### **Blade Selection Summary**

To see how TPI and width of the blade come together, use the table opposite for reference.

Regularly examine the blade for excessive damage or cracking as a result of fatigue. If such damage is present replace the blade.

It is important to use a sharp blade. Dull teeth result in increased feed pressure producing a poor quality finish and an inaccurate cut.



**ote:** As well as the blades listed, we can also supply bandsaw blades to almost any specification please call Record Power Customer Services in your country.


#### Record Power SABRE-350 Blade Range

Record Power's high performance bandsaw blades are manufactured to the highest quality tolerances using a specialist premium high carbon steel strip.

The extensive quality control program which involves digital tooth profile checks, set analysis, straightness testing, hardness testing and micro structural analysis results in a blade that cuts straighter and has harder, longer lasting teeth. A premium British blade that can last up to ten times longer than other blades on the market. To order any of these blades please contact Record Power Customer Services in your country who will advise you of your nearest retailer or alternatively a mail order supplier.

<b>BB1111406</b> 103-1/2"	1/4"	6.35 mm x 6 TPI Bandsaw Blade
<b>BB1113806</b> 103-1/2"	3/8"	9.5 mm x 6 TPI Bandsaw Blade
<b>BB1111204</b> 103-1/2" x 1	1/2"	12.7 mm x 4 TPI Bandsaw Blade
<b>BB1111206</b> 103-1/2"	1/2"	12.7 mm x 6 TPI Bandsaw Blade
<b>BB1115804</b> 103-1/2"	5/8"	15.8 mm x 4 TPI Bandsaw Blade
<b>BB1113403</b> 103-1/2"	3/4"	19.05 mm x 3 TPI Bandsaw Blade
<b>BB1113406</b> 103-1/2"	3/4"	19.05 mm x 6 TPI Bandsaw Blade

Wide Blade




Narrow Blade

#### **Custom igs Work Support**

A bandsaw is one of the most versatile machines in the workshop and with careful preparation many problems encountered on a job can be overcome. By making and using custom jigs repetitive and accurate work can easily be achieved, the following illustrations are some examples of typical jigs and supports used on a bandsaw.

Ex. 1. Supporting large workpieces with roller stands or take off tables.







Before carrying out any adjustments or maintenance ensure that the machine is isolated and disconnected from the electricity supply.

#### **Replacing the Drive Belt**

Remove the bandsaw blade and loosen the belt tension as shown in **Fig 10.1** by turning the tension hand wheel clockwise.

Remove the drive belt from the motor pulley and tension pulley as shown in **Fig 10.2**.


Remove the hex head socket screw with a 6 mm hex wrench and take off the washer from the lower band wheel hub, **Fig 10.3**.


Carefully pull the wheel from the shaft as shown in Fig 10.4.


The drive belt can now be removed and replaced. Place the new drive belt over the required band wheel pulley as shown in **Fig 10.5** and replace the band wheel.





Before replacing the band wheel it is advisable to clean out any build up of sawdust as access is much easier.











Ensure that the V grooves of the belt mate with the V grooves of the pulleys as shown in **Fig 10.6**.

Fit the drive belt onto the motor pulley and re-apply the drive belt tension.



The belt is correctly tensioned when it moves no more than approximately 6 mm 1/4 under reasonable pressure from the fingers. If the belt is slipping the tension must be increased and if it is wearing excessively the tension must be decreased.

The SABRE-350 can run at either 440.5 m / min or 899.2 m / min. The higher speed is suitable for cutting wood and the lower speed is suitable for cutting non-ferrous metals.

To set the machine at the lower speed, position the drive belt on the lower band wheel pulley and motor shaft pulley as shown in **Fig 10.7**.

To set the machine at the higher speed, position the drive belt on the lower band wheel pulley and motor shaft pulley as shown in **Fig 10.8**.

When changing the position of the drive belt ensure that it is also placed over the tension pulley as shown in **Fig 9.22**.


#### **Replacing the Band Wheel Bearings**


The bandsaw blade and wheels must be removed before replacing the bearings. To remove the lower band wheel follow the instructions in the section **Replacing the Drive Belt**.


To remove the upper band wheel, remove the hex head socket screw with a 6 mm hex wrench and take off the washer from the band wheel hub, **Fig 10.9**. The wheel can now be taken off the shaft.


The wheel hub contains 2 bearings and a spacer. This assembly is held in place on both sides with circlips as shown in **Fig 10.10**.


Remove the circlips from the rear and front of the wheel as shown in **Fig 10.11**.











Place the band wheel on 2 blocks of wood as shown in **Fig 10.12** and using a brass drift carefully tap out the bearings and bearing spacer from the inside of the band wheel.

Fit the new bearings either side of the spacer making sure to not hit the centre race of the bearing then re fit the two circlips. Then re-assemble the machine. When replacing use a piece of brass or similar material that is almost the same diameter as the outer race.



Knocking a bearing on the inner race that is a press fit on the outer race may cause instant damage to the bearing.

#### **Replacing Band Wheel Tyres**

The band wheels have rubber tyres fitted to protect the teeth of the blade when in use and also provide grip to stop the blade slipping. Regularly inspect the tyres for wear and damage and replace if necessary.

Remove the wheel from the bandsaw and ease the existing tyre from the rim, taking care not to damage the bandwheel.

Place the new tyre in hot water to soften and expand it. This will make it easier to fit onto the wheel.


Carefully fit the new tyre over the wheel and ensure it is placed centrally on the rim over the full circumference of the wheel as shown in **Fig 10.13**.


#### **Replacing Side Blade Guide Bearings**


To remove the side guide assembly fully unscrew the lock and remove the assembly as shown in **Fig 10.14**.


Remove the old bearing and replace with the new, ensuring the bearing bush, washer, bearings and sleeve are positioned as show in **Fig 10.15** and the assembly is screwed back into the quide shaft as shown.











#### **Replacing The Rear Blade Guide Bearing**

To remove the rear guide assembly fully unscrew the lock and remove the assembly as shown in **Fig 10.16**.

Remove the old bearing and replace with the new, ensuring the bearing bush, washer, bearings and sleeve are positioned as show in **Fig 10.15** and the assembly is screwed back into the guide shaft as shown.

Adjusting and Replacing the Band Wheel Brush and Blade Brush These brushes are located in the lower band wheel box as shown in Fig 10.18.

The purpose of the band wheel and blade brush is to remove sawdust that has been deposited during use.

To replace the brushes use a 10 mm wrench to remove the M6 nylon locking nut, washer and M6 x 25 bolt, replace the brush and re-assemble.

#### **Changing the Table Insert**

The table insert, **Fig 10.19**, is designed to give support to the workpiece and be soft enough to not cause damage to the blade if contact is made. The table insert will need to be replaced periodically as it wears.



### Removing the blade before removing the table insert will eliminate the risk of injury from the blade.

Push the table insert up and out from the underside of the table and fit the new table insert by pressing firmly down into place.

#### **Cleaning the Table**

Regular cleaning of the table will ensure optimum performance of the machine. Remove all dust and resin using white spirit then coat the table with Record Power **CWA195** Silicone Spray. The silicone spray will repel dust and resin, helping the timber to move freely on the table.

Only apply silicone spray if you are sure it will not affect any surface finish that will be applied to your project afterwards.


#### **Mechanical Motor Brake**


The machine is fitted with a mechanical motor brake which should be checked weekly to ensure that it functions correctly.


Test the brake with the blade mounted and correctly tensioned. Allow the machine to run up to full speed and then press the stop button on the switch. The blade should come to a complete stop within 10 seconds of the button being pressed.


If the brake does not function correctly, there are no user serviceable parts within the motor, so the motor unit must be replaced as a complete unit. If a replacement motor is needed, please contact Record Power Ltd or their local representative in your country for further assistance. The expected life of the brake components is 20,000 start/stop cycles.

The machine must not be used if the mechanical brake is not functioning correctly.









#### **Safety Devices**

The machine is fitted with various safety devices which should be checked weekly to ensure that they function correctly.

The doors of the machine are fitted with interlocking micro-switches designed to stop the machine if the doors are opened when the machine is in use **Fig 10.20**.


Testing of the micro-switches is best done without the blade fitted to the machine.

To perform the test, first close both doors and start the machine. With the machine running, open the upper door. The machine should stop as the door is opened. If the machine fails to stop, the micro-switch may require adjustment or cleaning in order for it to work correctly. If the micro-switch is found to be faulty, then it must be replaced immediately with a direct replacement part.

Repeat the same test with the lower door.

Finally, with the machine switched off, open both the upper and lower doors, and attempt to start the machine. The machine should not start. If the machine does start, the micro-switches may be faulty and should be replaced immediately.

If either of the micro-switches is found to be faulty or defective, the machine must not be used until suitable replacement parts have been fitted and proved to be working correctly.



### 11. Dust Extraction

#### The Importance of Dust Extraction

Suitable dust extraction is essential to avoid the possibility of serious health problems related to wood dust. It is also necessary in order to ensure the waste producing machine performs safely and effectively. Some woods are extremely toxic and in addition to suitable dust extraction machines it is recommended that PPE such as respirators are also used.

#### **Record Power Dust Extraction Machines**

Below is a summary of the Record Power range. Please visit your local stockist or go online for full details.

#### **DX1000 Fine Filter 45 Litre Extractor**

45 litre capacity, 1 kW motor, 0.5 micron filtration. Includes hose.

#### **RSDE1 Fine Filter 45 Litre Extractor**

45 litre capacity, 1 kW motor, 0.5 micron filtration. Includes hose.

#### RSDE/2 Fine Filter 50 Litre Extractor with Accessories

50 litre capacity, 1 kW motor, 0.5 micron filtration, includes wheel kit, hose cuff power tool adaptor hose and spare filter bags. Includes hose.

### RSDE/2A Fine Filter Auto-Switching 50 Litre Extractor with Accessories

50 litre capacity, 1 kW motor, 0.5 micron filtration, includes wheel kit, hose cuff power tool adaptor hose and spare filter bags. Includes hose.

#### **DX4000 Fine Filter Twin Motor 80 Litre Extractor**

80 litre capacity, 2 x 1 kW motors, 0.5 micron filtration. Includes hose.

#### **DX5000 Fine Filter Twin Motor 200 Litre Extractor**

200 litre capacity, 2 x 1 kW motors, 0.5 micron filtration. Includes hose.

#### **CGV286 CamVac Series Compact Extractor**

36 litre capacity, 1 kW motor single or twin, 0.5 micron filtration.

#### CGV286-WALL CamVac Series Wall Mounted Extractor

150 litre capacity, 1 kW motor single or twin, 0.5 micron filtration.

#### **CGV336 CamVac Series Medium Extractor**

55 litre capacity, 1 kW motor single or twin, 0.5 micron filtration.

#### CGV386 CamVac Series Large Extractor

90 litre capacity, 1 kW motor twin or triple, 0.5 micron filtration.

#### **CGV486 CamVac Series Heavy Duty Extractor**

200 litre capacity, 1 kW triple motor, 0.5 micron filtration.

#### **CX2000 Compact Chip Collector**

54 litre capacity, 0.56 kW motor. Includes hose.

#### CX2500 80 Litre Chip Collector

80 litre capacity, 0.55 kW motor. Includes hose.

#### **CX3000 Heavy Duty Chip Collector**

128 litre capacity, 0.56 kW motor. Includes hose.

### **AC400 2 Stage Air filter with Remote, 3 speeds and Time Delay** Collects airborne dust, 1 micron filtration.

Collects all bottle dust, i fillcroft littration.





Recommended for light / intermittent use



Can be used

•	Bandsaws	Table Saws	Planer Thicknessers		Sanding Machines	Dust Extraction Systems	Airborne Dust Collection
DX1000	-	-			-		
RSDE1	<b>*</b>						
RSDE/2	-	<b>*</b>			-		
RSDE/2A	-	<b>*</b>					
DX4000	<b>~</b>	<b>~</b>		<b>~</b>	<b>~</b>		
DX5000	<b>~</b>	<b>~</b>		<b>*</b>	<b>~</b>	<b>*</b>	
CGV286	-	<b>*</b>			-		
CGV286-WALL		<b>*</b>	-			<b>*</b>	
CGV336	-	<b>*</b>					
CGV386	<b>~</b>	<b>~</b>		<b>~</b>	<b>*</b>		
CGV486	<b>~</b>	<b>~</b>		<b>~</b>	<b>~</b>	<b>*</b>	
CX2000	•		<b>~</b>				
CX2500		•	<b>~</b>				
CX3000			<b>~</b>	<b>~</b>			
AC400							<b>~</b>

# 12. Troubleshooting

Problem	Cause	Solution
Will not cut in a straight line.	1. Blade is blunt.	1. Change blade.
-	2. Blade guides set too high.	2. Adjust blade guides.
	3. Blade tension incorrect.	3. Adjust blade tension.
	4. Fence aligned incorrectly.	4. Align fence as shown in <b>section 8</b> .
	5. Table aligned incorrectly.	5. Align table as shown in <b>section 8</b> .
Motor slows down during cutting.	1. Too much pressure being applied.	1. Adjust feed rate to suit material being cut.
	2. Drive belt slipping.	2. Adjust drive belt tension.
	3. Fence aligned incorrectly.	3. Align fence as shown in <b>section 8</b> .
	4. Table aligned incorrectly.	4. Align table as shown in <b>section 8</b> .
	5. Wrong type of blade being used.	5. Change blade to a suitable type.
Machine only operates when pressure is applied to the on switch.	1. Faulty switch.	1. Replace switch.
Machine buzzes but will not run.	1. Motor capacitor is faulty.	1. Replace motor capacitor.
Blade cannot be tted.	1. Blade tension not released.	Release blade tension using the blade tension lever. Further tension reduction may be need to be performed using the blade tension knob.
	2. Blade is too small.	2. Ensure the correct length of blade is used.
Blade cannot be tensioned suf ciently.	1. Blade is too long.	1. Ensure the correct length of blade is used.
Blade will not cut.	1. Blade is upside down.	Ensure the teeth of the blade point downwards towards the bandsaw table.
	2. Blade is back to front.	<ol><li>Ensure the teeth of the blade point towards the front of the machine.</li></ol>
The bandsaw will not start.	1. o power supply.	Ensure the machine is connected to a suitable power source.
	2. Faulty switch.	2. Replace the switch.
	3. Doors not fully closed.	3. Ensure both doors are fully closed.
	4. Fuse blown.	4. Replace the fuse.
	5. Faulty motor.	<ol><li>Replace the motor with a genuine Record Power motor.</li></ol>
The bandsaw blade does not move when the motor is running.	1. The blade is under insuf cient tension.	Ensure suf cient tension is applied to the blade.
	2. The blade has come off the wheels.	Re- t the blade and ensure it is correctly tracked and tensioned.
	3. The blade has broken.	3. Replace the blade.
	4. The drive belt has broken.	4. Replace the drive belt.
The bandsaw will not cut at 45 or 90 to the table.	1. The table angle is incorrectly calibrated.	Set the table at 90 to the blade and re-set the angle pointer if necessary.
	2. The blade is blunt.	2. Replace the blade.
	3. Excessive pressure is being applied.	3. Reduce feed rate of the workpiece.

### 13. Electrical Connection and Wiring Diagram

Machines supplied for use in the " are tted with a 3 pin plug conforming to BS1363, tted with a fuse conforming to BS1362 and appropriate to the current rating of the machine.

Machines supplied for use in other countries within the European "nion are tted with a 2 pin Schuko plug conforming to CEE 7/7.

Machines supplied for use in Australia ew ealand are tted with a 3 pin plug conforming to AS/ S3112.

In all cases, if the original plug or connector has to be replaced for any reason, the wires within the mains power cable are colour coded as follows

#### 230 V Single Phase

Brown Live L
Blue eutral
reen and Yellow Earth E

The wire coloured brown must always be connected to the terminal marked L or coloured red.

The wire coloured blue must always be connected to the terminal marked or coloured black.


The wire coloured green and yellow must always be connected to the terminal marked E or with the earth symbol




or coloured green / green and yellow.

In the case of the BS1363 plug for use in the ", always ensure that it is tted with a fuse conforming to BS1362 appropriate to the rating of the machine. If replacing the original fuse, always t a fuse of equivalent rating to the original. ever t a fuse of a higher rating than the original. ever modify the fuse or fuse holder to accept fuses of a different type or size.


If a plug conforming to BS1363 is used, the combination of plug and socket shall be protected from water and dust to at least IP44.






I-JL28010003-001S I-JMBS1401011000B-051W I-JL27010005	uide post cap	_	47	1-JMBS1401013001	ower allique	
011000B-051W 05		-	2		LOWER GUIDE	<b>—</b>
)5	Frame	<del>-</del>	48	1-JMBS1403014008	Spring	<b>—</b>
	Batter board	_	49	1-JMBS1403014004	Lower guide shaft	_
-JL81100003-016S	Push stick	_	20	1-M8 12 B70D2B	Screw M8 x 12	_
-M6 B6170B	ex nut M6	_	51	1-WS 8 B96D1B	Large washer	-
-M6 30 B70D1B	ex bolt M6	_	52	1-M8 8 B80B12D9	ex nut M8	_
-JMBS1401010005A	Thread plate	4	53	1-1904011	andle nob	_
-RVT4 8 B12618A	Rivets	4	54	1-JMBS1401012001	Camshaft rod	_
-JMBS1401014000-053W	"pper door	_	55	1-JMBS1403016004	Cam	_
-8101-1025F	Plastic hinge	4	26	1-JMBS1403016003	Tension	_
-M4 12 B70D3B	Screw M4 x 12	∞	57	1-JMBS1403030004	eel block	<b>—</b>
-M6 16 B70D3B	ex socket screw	∞	58	1-WS 10 B849B	Washer	<b>—</b>
-JL26010001	lass window	_	59	1-M10 B6170B	ut M10	7
-JMBS1401010003B-053W	Lower door	<b>-</b>	09	1-JMBS1401010001	Lower guide connecting plate	<b>—</b>
-M4 10 B818B	Pan head screw	13	61	1-WS 5 B97D1B	Flat washer	c
-M6 B889D1	Self-locking nut	2	62	1-M5 12 B70D1B	ex socket head screw	9
-JL26010007	Sleeve	7	63	1-M6 10 B77B12D9	Set screw	<b>—</b>
-M6 20 B70D1	ex socket head screw	2	64	1- TSB-1-B-M6 50 10	Adjusting handle	<b>—</b>
-M5 10 B70D2	Screw M5 x 10	_	65	1-ST3D5 9D5 B845B	Self tapping screw	7
5 B97D1	Flat washer	_	99	1-JL20010007-001S	Dust port	_
-JL27010004-114	Tension indicator arrow	_	29	1-M6 B6170B	ut M6	_
-JL26010010	Screw	_	89	1-JMBS1401010004	Connecting plate	_
-JL27010019	Screw	_	69	1-M6 30 B77B	Set screw	<del>-</del>
-M4 10 B823B	Pan head screw	4	70	1-J BS2401010018	Plastic tubing	<b>—</b>
	On/Off switch	_	71	1-JL28041004	Cover	2
-M5 12 B70D1B	Cylinder head screw	<del>-</del>	72	1-JL21010014	eel block	<b>—</b>
B6170B	nt	<b>—</b>	73	1-JL26010015	Stud shaft	_
8 B97D1B	Flat washer	<del>-</del>	74	1-JMBS1403011026-053W	Pointer	_
-M8 B889D1B	Self-locking nut	_	75	1-M6 25 B70D1	ex socket head screw	7
-JMBS1401010002-001S	Lower guide guard	_	9/	1-JL26010006-001S	andle	7
-WS 6 B97D1B	Flat washer	2	77	1-M6 B889D1	Self-locking nut	7
16 B70D1B	Screw	<del>-</del>	78	1-P224E-13A	Single-phase plug	_
-M6 B889D1	Self-locking nut	_	79	1-JL28010005-001S	Dust board	<del>-</del>
-JL26010003	Brush	_	80	1-M5 10 B818B	Pan head screw	7
-WS 6 B96D1	Large washer	<b>—</b>	81	1-JL26090001	Tool holder	<b>—</b>
-M6 25 B5783	ex bolt M6 x 25	<b>—</b>	82	1-M4x16 B818	Pan head screw	4
-JL20010019-001S	Dust port grating	<b>—</b>	83	1-JL91046100	Cable gland	_
-M4 30 B818	Pan head screw	4	84	1-M8 25 B5783B	ex socket head screw	4
	Micro switch	2	82	1-M8 B6170B	ut M8	4
-JMBS1401010006A-117"	Micro switch seat	2	98	1-JMBS1401015100-051W	Plate	_
-JMBS1403014005	Spring	2	87	1-3RT6018-1A 21	AC contactor	<b>.</b>
-JMBS1403014006-001S	Locking handle	m	88	1-JMBS1401010009	Support plate	_
-JMBS1403014002	Bearing sleeve	m	88	1-M6 B6172D1	Thin nut	7
-BR 6202-2RS B276	Bearing	m	06	1-JMBS1401010011	Sleeving	7
I-WS 8 B96D1B	Large washer	m	91	1-M6 60 B70D1	Screw M6 x 60	2
1-JMBS1403014003	uide shaft	2				

#### **Driving System Assembly**




0	Part number	Description	ty	0	Part number	Description	ty
1	1-JL28020001C	Blade	1	17	1-JL20020004	ex. nut	1
2	2-YY 900114A	Motor	1	18	1-CLP17 B894D1B	Retaining ring	1
3	1-WS 6 B96D1	Large washer	4	19	1-CLP40 B893D1B	Circlip ring	4
4	1-WS 6 B93	Spring washer	4	20	1-BR 6203-2RS B276	Bearing	4
5	1-M6 16 B70D1	Screw	4	21	1-JL28020004	Bearing spacer	2
6	1-JL20014001	Tension roller shaft	1	22	1-WS 8 B5287	Large washer	2
7	1-BR 6001-2RS B276	Bearing	2	23	1-M8 16 B70D1	ex bolt	2
8	1-CLP28 B893D1B	Circlip ring	2	24	1-WS 8 B93	Spring washer	2
9	1-JL20014002A	Tension roller	1	25	1-JL28022001-053	"pper wheel	1
10	1-CLP12 B894D1B	Retaining ring	1	26	1-JL26020014B-001S	Small handle	1
11	1-M6 8 B80B12D9	ex bolt	2	27	1-S SL-D100-d10A	andwheel	1
12	1-JMBS1401020003A	Motor pulley	1	28	1-M6 8 B77B12D9	ex socket set screw	1
13	1-4PJ635 B16588	Belt	1	29	1-M5 8 B71	Screw	2
14	1-JL28023001-053	Lower wheel	1	30	1-CLP10 B884D1	Circlip ring	2
15	1-JL21022002B	Tyre	2	31	1-JL28020003A	Threaded rod	1
16	1-JL28020002A	Lower wheel shaft	1				

Table Assembly




0	Part number	Description	ty	0	Part number	Description	ty
1	1-M6 4 B77B12D9	Set screw	2	15	1-M6 12 B77B	Set screw M6 x 12	4
2	1-JMBS1401030100-001L	Table	1	16	1-JMBS1403030005	Support bracket	1
3	1-JMBS1404030002	Table support pin assembly	1	17	1-WS 10 B97D1B	Flat washer	2
4	1-WS 4 B96D1	Large washer	1	18	1-WS 10 B93B	Spring washer	2
5	1-M4 10 B818	Pan head screw	1	19	1-J BS2401031008A	Table angle pointer	1
6	1-M8 B6170B	ut M8	1	20	1-M3 5 B818	Pan head screw	1
7	1-M8 50 B5781B	ex bolt M8 x 50	1	21	1-JMBS1401032001	ear shaft	1
8	1-JMBS1403030002	Lower table trunnion	1	22	1-JL29050002	Socket spanner	1
9	1-WS 8 B96D1B	Large washer	4	23	1-JMBS1403030003	Rack	1
10	1-WS 8 B93B	Spring washer	4	24	1-JMBS1403030008	Eccentric bushing	1
11	1-M8 25 B70D1B	ex socket head screw	4	25	1-M6 16 B70D1B	Screw M6 x 16	1
12	1-M10 25 B5783B	ex bolt M10 x 25	2	26	1-M8 16 B70D3	ex countersunk head screw	3
13	1-WS 12 B97D1B	Flat washer	1	27	1-RVT2D5 5 B827C	Rivet	3
14	1-M12 B889D1B	ex locking nut	1	28	1-JMBS1403030006	Angle scale label	1

### **Blade Tension Assembly**




0	Part number	Description	ty	0	Part number	Description	ty
1	1-JMBS1001043001-001S	Tension knob	1	15	1-M3 B6170B	ut -	1
2	1-JL28032000B	Connecting sleeve	1	16	1-BR 51104 B301	Bearing	1
3	1-WS 12 B97D1	Flat washer	1	17	1-JL28033000	andle Rod	1
4	1-M6 12 B70D1	ex socket head screw	2	18	1-1904011	andle nob	1
5	1-WS 6 B5287	Large washer	2	19	1-JL28030007	Sliding block	1
6	1-JL28030008	Support shaft	1	20	1-PI 5 24 B879D1B	Roll pin	1
7	1-JL28030003	ut	2	21	1-JL28030005	Stud shaft	1
8	1-JL28031000	Tension bracket	1	22	1-JL20010016A-001S	Wing nut	1
9	1-JL28030001	Sleeve	1	23	1-J PT1201060013-001S	Adjusting knob	1
10	1-JL28030010	Sliding block guide rail	1	24	1-JL28030009	Washer	1
11	1-JL28030004	" pper bearing bolt	1	25	1-WS 6 B97D1B	Flat washer	3
12	1-JL27030011A	Spring	1	26	1-WS 6 B93B	Spring washer	3
13	1-JMBS1404040100	Plate	1	27	1-M6 14 B5781B	ex. bolt M6 x 14	3
14	1-M3 16 B70D2B	ex head screw	1				

**Upper Guide Assembly** 




0	Part number	Description	ty	0	Part number	Description	ty
1	1-JMBS1801050005-001S	Lock handle	1	24	1-JMBS1403014008	Spring	1
2	1-M6 16 B5783B	ex bolt M6 x 16	4	25	1-JMBS1401050001	"pper guide support block	1
3	1-WS 6 B96D1B	Large washer	4	26	1- TSB-1-B-M8 63 20	Lock handle	1
4	1-JL27040006	uide bracket	1	27	1-JMBS1401051002	uide supporting rod	1
5	1-M6 12 B77B	Set screw M6 x 12	4	28	1-M8 10 B77B	ex. socket set screw	1
6	1-1501006	ear	1	29	1-JMBS1403014004	Adjust bar	1
7	1-JL26040006	Screw	1	30	1-M5 25 B70D1B	Screw	1
8	1-JL26040007	Fixed plate	1	31	1-JMBS1401050002A	Slider bar	1
9	1-JL27040002A	uide bracket cover	1	32	1-M5 10 B818B	Pan head screw	2
10	1-M6 16 B70D1	ex bolt	4	33	1-JL28040001A	Rack	1
11	1-JMBS1401050006	Spring piece	1	34	1-M5 8 B819D1B	Screw	3
12	1-WS 6 B96D1	Large washer	1	35	1-JMBS1401050003	Scale	1
13	1-M6 10 B70D1	ex socket head screw	1	36	1-JMBS1401052000A-114	Saw blade guard	1
14	1-JMBS1401051003-001S	Lock handle	1	37	1-WS 5 B97D1B	Flat washer	2
15	1-JMBS1401051004	Sleeve	1	38	1-M5 12 B70D1B	ex socket head screw	2
16	1-JMBS1403014003	uide shaft	2	39	1-M6 12 B77B	Locking screw M6 x 12	1
17	1-JMBS1403014002	Bearing sleeve	3	40	1-S SL-D100-d10A	Crank hand wheel	1
18	1-JMBS1401051003-001S	Lock handle	2	41	1-JL26020014B-001S	Small handle	1
19	1-JMBS1401051004	Sleeve	2	42	1-JL20010015	Set screw collar	1
20	1-BR 6202-2RS B276	Bearing	3	43	1-M5 8 B71B12D9	Set screw M5 x 8	1
21	1-WS 8 B96D1B	Large washer	3	44	1-JL27040003	Bushing	1
22	1-JMBS1403014005	Spring	2	45	1-JL27040004	Worm cylinder	1
23	1-JMBS1401051001	"pper guide	1			•	

### **Rip Fence Assembly**



0	Part number	Description	ty
1	1-JMBS1403060009-001S	Adjust handle	1
2	1-JMBS1403060010-001S	Drift locking handle	1
3	1-M8 10 B80B	ex screw	1
4	1-JMBS1403060004	Cam	1
5	1-WS 10 B97D1	Flat washer	6
6	1-M10 B889D1	ex locking nut M10	1
7	1-JMBS1403060003-001S	Fence locking handle	1
8	1-WS 8 B96D1	Large washer	1
9	1-JMBS1403060001-053W	Fence carrier	1
10	1-JMBS1401063100	Locking handle	1
11	1-JMBS1403060007	Spring	1
12	1-JMBS1403060005	Sliding block	1
13	1-JMBS1403061002	Bolt	1
14	1-JL26061003	Bolt	1
15	1-JMBS1403061001	Bar	1
16	1-JMBS1403060006	uide rail	1
17	1-J BS2001060003	Connecting rod	2
18	1-M10 B6170	ex nut	4
19	1-M6 16 B77B12D9	Set screw	2
20	1-JMBS1401060001	ylon plate	2
21	1-JMBS1404060001	Fence	1
22	1-JL93010018	Spacer	2
23	1-WS 6B97D1B	Flat washer	1
24	1- TSB-1-A-M6 50	Lock knob	1
25	1-PI 6 26 B879D1B	Roll pin	1

### **Cabinet Base Assembly**



0	Part number	Description	ty
1	1-M6 16 B70D1	ut	1
2	1-JL20010001A	Bushing	1
3	1-M6 B889D1	Self-locking nut	2
4	1-JL28051000-053W	Door assembly	1
5	1-M6 40 B70D3	ex socket screw	4
6	1-JL28050002A-053W	Left side panel	1
7	1-WS 8 B96D1	Large washer	4
8	1-JL28050001A-053W	Back side panel	1
9	1-M6 20 B70D1	ex socket head screw	1
10	1-JL26010006-001S	andle	1
11	1-JL28050006A-053W	Right side panel	1
12	1-JL28050004-053W	Shelf	1
13	1-JL28050003A-053W	Beam	2
14	1-M8 20 B5789	ex bolt M8 x 20	16
15	1-JL28050005B-053W	Base board	1

### E" Declaration of Conformity

#### Cert o: EU / SABRE-350 / 1

#### **Record Power Ltd**,

Centenary ouse, 11 Midland Way, Barlborough Links, Chesterfield, Derbyshire, S43 4 A, " declares that the machinery described -

1. Type	Band	lsaw
---------	------	------

<ol> <li>IVIOUEL HUITIDEL JADRE-3:</li> </ol>	2.	Model	number	SABRE-35	0
---	----	-------	--------	----------	---

3.	Serial	0	

Conforms with the following directives -

MAC I ERY DIRECTIVE 2006/42/EC


ELECTROMA ETIC 2014/30/E" COMPATIBILITY DIRECTIVE E 1807-1 2013

E 60204-1 2006 A1 2009 AC 2010

and conforms to the machinery example for which the EC Type-Examination Certificate o. BM 50374938 0001 has been issued by **TUV Rheinland LGA Products GmbH** at Tillystrasse 2, D90431 rnberg

and complies with the relevant essential health and safety requirements.

**Andrew Greensted** Managing Director





### Woodworking Machinery and Accessories

Record Power Ltd, Centenary ouse, 11 Midland Way, Barlborough Links, Chesterfield, Derbyshire S43 4 A

Tel 44 0 1246 571 020 Fax 44 0 1246 571 030 www.recordpower.co.uk

To register a product and find your local stockist visit

recordpower.info